

# The LOFAR phase II cluster (update)


Chris Broekema

on behalf of

Harm Paas (RUG), Teun Grit, Arjen Koers (RUG) and Andre Gunst

# LOFAR New Year's Resolutions

- More taart (i.e. nice results).
- More short LSM presentations about observational and reduction results.
- Communicate more between groups.





ASTRON

NWO



# Current status

- Bi-weekly planning / scheduling meeting
- LSM updates for foreseeable future
- ClusterVision finished preparing the racks
  - All rails, cables and switches in place
- First pilot hardware has arrived
  - Testing of the base software stack
- Burn-in testing of the rest of the hardware
- Expected start of installation: 7<sup>th</sup> February

# Current status

- First networking steps taken Jan. 17<sup>th</sup>
  - Moved international stations to different switch
  - Migrated to new station – BG/P connection scheme
- Next: move phase 1 to make room for phase 2
  - Planned for Feb. 7<sup>th</sup>
  - Will involve disruption of service to phase 1 cluster
- Zernikeborg – Landleven trunk expected soon
- Pilot hardware available to pilot users very soon
  - Port software stack and pipelines



**ASTRON**

**NWO**




**ASTRON**

**NWO**



**ASTRON**

**NWO**








**cluster vision**

**ASTRON**

**NWO**









**\* Hardware installation [25%]**

- Responsibility ClusterVision
- pilot hardware
- install all nodes
- connect network to patch panel
- DOA test of all equipment

**\* Network [50%]**

- Blue Gene rack R02-M1 less IO rich
- Add extra 10G module RX16 Core
- Move phase 1 cluster from Core to BG-L
- Add patches for phase 2 cluster
- Configure ports for phase 2 cluster
- Add patches for Target
- Configure ports for Target
- Move international stations to BG-L
- Add shortcut links from BG-L to BG0 - BG3
- Connect RS205 to port reserved for RS410
- Arrange patch panel for TARGET
- Arrange patch panel for Phase II cluster
- Connect LOFAR to IAS-4 cluster

**\* Bridge configuration [x]**

- Install three bridge nodes in default configuration
- Configure Blue Gene to use single bridge for first tests
- Design a way to divide bridges among IO nodes efficiently
- Use fourth node for experiments to increase performance

**\* OS installation [33%]**

- build and install a central node that can provide services that will not travel through the bridge
- new bootleg image using 10.04 LTS
- test and roll-out

**\* Acceptance tests [x]**

- Bandwidth test from Blue Gene to disk
- Store 35 Gbps raw data from Station beamformer for offline correlation (requested)

**\* Porting applications [x]**

- Make one new frontend node available to pilot users ASAP
- Make sure all installed applications on the old cluster are ported to the new cluster
- Have RO point out pilot users that will actively port the applications when frontend is available

**\* Migrate production**

- do full production run on new hardware
- In this period the old phase 1 cluster will still be available for production while we bring the new phase 2 cluster online.

**\* Migrate staging [x]**

- Configure at least one of the four partitions as part of a distributed filesystem
  - Test pvfs2
- Install gridftp client
- Configure connection to LTAs

**\* Migrate development [x]**

- Add distributed filesystem mount to nodes
- probably divide cluster into three components with varying size:
  - Development of offline algorithms
  - Commissioning work
  - Compute intensive tasks not directly related to production
- We may need to configure a cluster scheduling tool for the last task
  - Does anyone have experience with a scheduler?

**\* Commissioning [100%]**

- Migrate LOFAR system to new connection scheme
- Make sure optimized network configuration is correctly implemented

