Thinking Infrastructure

MIDPREP/AAMID Workshop, Cape Town





SQUARE KILOMETRE ARRAY

Exploring the Universe with the world's largest radio telescope

Tracy Cheetham 8 March 2016


Overview of presentation



- Overview of the South African site
- Summary of existing MeerKAT infrastructure delivered
- SKA1_MID baseline infrastructure & power design (PDR) & challenges
- MFAA demonstrator requirements
- Infrastructure, power and other considerations to meet these requirements
- Looking ahead to SKA2




South African Site & Protection



SKA Locality Plan





MeerKAT Infrastructure






Greenfields to Observatory





Long-haul fibre to Cape Town









MAR SKA MID

radio telescope



New 33 kV Powerline with MASS fibre optic cable approaching Core Site



60

mill

Above: New 33kV grid power line to SKA site

Right: Upgrade of Karoo substation to 10MVA

Exploring the Universe with t

MeerKAT Infrastructure





Buildings





MeerKAT Infrastructure






SKA1_MID baseline design (PDR)








SKA1_MID Physical Configuration



Exploring the Universe with the world's largest radio telescope



Land in "Core" area to be acquired




SKA1_MID Site Studies



- LIDAR survey completed of 390,000 hectare area
- Geotechnical investigation underway
 - Completion date June 2016
- Geohydrological investigation & flood line analysis underway
 - Completion date June 2016
- Strategic Environmental Assessment underway
 - Heritage, flora, fauna, agriculture, archaeological, agriculture, socio-economic impact, visual impact

MeerKAT / SKA1_MID Core






Access

- Approximately 560km of road works required for SKA1_MID
- Of the 560km, 150km will be new roads in the spiral arms; 12km will be new roads in the core and 398km in the spiral arms will be existing farm & district roads which will be rehabilitated to improve access
- Roads will follow independent routing of power line & have separate servitudes


Grid Power – SKA1_MID








Grid Power – current solution



Power to Spiral Arms






Standalone PV Investigation




- SKAO has raised ECP to undertake feasibility study to determine whether the antennas in the spiral arms can be supplied via standalone photovoltaic installation
- PV System performance requirements are still being investigated. Once this has been defined, the system will be costed
- PV System will be sized based on Meteo Data for the Karoo Site using an estimated load of 11.5kW (Peak) per dish
- Risks: RFI & separation distances, additional land requirements, storage requirements, maintenance etc.


Power Reticulation in Core







Buildings







INFRA Construction Deployment

- Propose "big-bang" approach where infrastructure & power deployment in Core and 3 spiral arms concurrently & all activities are co-ordinated from a central point close to the core;
- Estimate 36 month construction period commencing in 2018
- Resources required for management and construction of Infrastructure & Power
- Grouping of construction work packages discussed
- Impact of SKA1_MID deployment on MeerKAT operations (e.g. power outages)




MFAA demonstrator requirements

- Location of MFAA demonstrator (refer to next slides)
- 5 stations with coverage area of 1000m²
- Power requirement: 200kW for 5 stations
- Configuration / baselines?
- Data requirement: 10Tbps per station?
- Data rack requirements?
- Anticipated deployment: 2020

MFAA demonstrator location

- MeerKAT and SKA1_MID core located on "K3 site"
- Proposal for MFAA demonstrator to be slightly away from MeerKAT/SKA1_MID core yet accessible
- Proposed location: "K4" site topography provides 360° shielding
- Part of K4 site owned by the NRF
- Area large enough for SKA2 MFAA expansion
- Some SKA1_MID southern spiral arm infrastructure can be re-used





MFAA demonstrator configuration

- Configuration assumed by INFRA for now
 - "star configuration"
 - centralized distribution of power and fibre to reduce costs
 - shared RFI-shielded container / bunker to reduce costs



MFAA Power supply options





Power challenges




- SKAO will be releasing updated SKA1_MID power budget shortly.
- The existing power budget estimates an average load of 4007kW and a peak load of 4865kW
- The figure above were based on an allowance of 590kW for CSP. The latest ICD from CSP indicates approximately 1000kW of power will be required with an extremely high uncertainty Adding roughly 500kW to the existing power budget would bring the peak load to around 5.3MW (excluding 200kW for MFAA demonstrator)

MFAA Power challenges




- Power provision for MFAA demonstrator (200kW) is likely to be problematic given current power constraints on site and escalating power budget
- Current thinking is that bulk power supply to site will have to be either upgraded / supplemented
- SKAO has established Power Options Working Group which will look at alternative power supply options (for SKA1 and SKA2) – could include storage facility along 33kV line; solar boost, static power correction, solar cooling etc.
- SKAO responsible for power generation / distribution to site
- Recommendation that the "best guess" power estimate for the demonstrator be submitted to the SKAO Power Engineer for inclusion in the SKA1_MID power budget.

MFAA Centralized processing



6m long, 3m wide, 2,4m high shielded container housing ~6 racks resting on 400mm reinforced concrete slab 400mm below NGL with brick retaining walls & channels







KAPB

SYMBOL	DESCRIPTION	QUANTITY
	MEERKAT EXISTING RACKS	45
80.295	MEERKAT TIME & FREQUENCY REFERENCE (MK TFR)	3
NF 016	MEERKAT GPS (MK GPS)	1
in and of	MEERKAT MASER UNIT (MK MASER UNIT)	2
	SKA1 SITE MONITORING	3
-	SKA1 TM	2
50-14	SKA1 AJV LMC	2
MATE:	SKA1 TIME & FREQUENCY REFERENCE (TFR)	3
DOLINARY. IN	SKA1 MASER UNIT	2
159-575	SKA1 GPS	1
	SKA1 SADT	15
	SKA1 CSP CBF (640mm WIDE RACKS)	18
	SKA1 CSP PST	2
-	SKA1 CSP PSS	40

• KAPB Data Rack area has no space for additional racks

Site Complex







MFAA demonstrator considerations

- Location confirmation of demonstrator & SKA SA Guest Instrument Policy to be concluded
- Number of stations
- Size of stations (diameter)
- Configuration of stations
- Power and data requirements
- Bunker? / container requirements
- Number of racks in central processing area; number of racks at Site Complex
- Ground preparation requirements
- Construction deployment of infrastructure makes sense to deploy SKA1_MID and MFAA demonstrator infrastructure at the same time
- Who is designing the demonstrator infrastructure and power?
- Environmental Impacts to be assessed through SEA process

Looking ahead to SKA2



- SKA2 configuration TBD
- Servitudes to be secured for stations in spiral arms (outside land to be owned by the NRF)
- Station numbers (250) and sizes (60mØ? each)
- Provision of power and data for SKA2 TBC MFAA power (30MW?) and data requirements (10Tbps / station?)
- Power and fibre distribution concepts
- Strategic Environmental Assessment for SKA2
- Topography (easy ground preparation) key to positioning of stations

SQUARE KILOMETRE ARRAY

Exploring the Universe with the world's largest radio telescope



Thank You